


15051-05541-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Ellis County, Sec. 23 Twp 13S Rge. 17W (E) (W)  
Location as "NE/CNW/SW" or footage from lines SW NW NE  
Lease Owner ALPINE OIL & ROYALTY CO., INC.  
Lease Name DINKEL Well No. 2  
Office Address 800 Bitting Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) oil well  
Date well completed May 27, 1955 19  
Application for plugging filed April 23, 1963 19  
Application for plugging approved April 24, 1963 19  
Plugging commenced April 27, 1963 19  
Plugging completed April 29, 1963 19  
Reason for abandonment of well or producing formation non-productive in commercial quantities  
If a producing well is abandoned, date of last production April 23 1963  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation Lansing-KC Depth to top 3266 Bottom 3496 Total Depth of Well 3549 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	200'	Cemented
				5 1/2"	3531	643'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set plug at 3300 feet and ran 5 sacks of cement from 3300 feet to 3770 feet. Pulled pipe to 500 feet and pumped 30 sacks of gel mud and 20 sacks of cement, pulled pipe to 200 feet and pumped 20 sacks of cement, pulled pipe to 30 feet and pumped 10 sacks of cement from 30 feet to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 8 1963

05-08-1963  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Glenn and Smith Pipe Pulling Company  
Address Box 114, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Thomas M. McCaul (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas M. McCaul  
800 Bitting Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of May, 1963

My commission expires August 10, 1965

Virginia M. ...  
Notary Public.

15-051-05541-00-00

WELL LOG

ALPINE OIL & ROYALTY CO., INC.

Commenced: 4-21-55

Contractor: Quaker Drilling Co., Inc.

Completed: 5-27-55

Dinkel No. 2  
SW NW NE Sec. 23-13S-17W  
Ellis County, Kansas

Elevation: 1996 K. B.

Production: 15 BOPD

**RECEIVED**  
STATE CORPORATION COMMISSION

APR 24 1963

04-24-1963

CHIEF CLERK  
MICHIGAN, KANSAS

**Casing Record:**


Set 200 feet of 8 5/8 inch with 55 sacks cement.  
Set 3531 feet of 5 1/2 inch with 150 sacks cement.

(Figures Indicate the Bottom of Formations)

<u>FORMATIONS</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>	
Surface Soil & Shale	80	Anhydrite	1170
Lime Shells & Shale	365	Heebner	3218 -1222
Sand	445	Lansing	3266 -1270
Shale & Streaks of		Base of Kansas	
Sand	545	City	3496 -1500
Shale	765	Conglomerate	3514 -1518
Sand	815	Arbuckle	3529 -1533
Shale	1000	Total Depth	3533 -1537
Shale & Shells	1170	(Rotary)	
Anhydrite	1210	Cable Tool Total	
Shale & Shells	1560	Depth	3549
Shale	1765		
Shale & Shells	1895		
Shale & Lime	2270		
Shale	2340		
Lime & Shale	3300		
Lime	3342		
Lime & Shale	3510		
Lime	3533		
Lime and Shale	3549		

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the SW NW NE of Section 23, Township 13 South, Range 17 West, Ellis County, Kansas.

QUAKER DRILLING CO., INC.

By:   
Thomas M. McCaul, President

SUBSCRIBED AND SWORN TO BEFORE ME this 21st day of July, 1955.

  
Notary Public

MY COMMISSION EXPIRES:  
August 10, 1957