


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

.....**Ellis**.....County. Sec. **23** Twp. **13** Rge. **17W** (E).....(W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines.....**SE SE SW**
Lease Owner.....**Darby & Bothwell, Inc.**
Lease Name.....**Reme "A"**.....Well No. **1**
Office Address.....**612 Orpheum Building, Wichita, Kansas**
Character of Well (completed as Oil, Gas or Dry Hole).....**Dry hole**
Date well completed.....**March 24, 1951**.....19
Application for plugging filed.....**March 27, 1951**.....19
Application for plugging approved.....**March 24, 1957 by Petty**.....19
Plugging commenced.....**March 24, 1951**.....19
Plugging completed.....**March 24, 1951**.....19
Reason for abandonment of well or producing formation.....**dry**
If a producing well is abandoned, date of last production.....19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?.....**Yes from Mr. Petty, Hays, Kansas**

Name of Conservation Agent who supervised plugging of this well.....**Petty**
Producing formation.....**Arbuckle**.....Depth to top.....**3560**.....Bottom.....**3566**.....Total Depth of Well.....**3566**.....Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Top Heebner	3220			8 5/8"	230	none
Lansing	3266					
Cherty Cong.	3511					
Arbuckle	3560					
Total Depth	3566					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.
Pumped hole full of heavy drilling mud to 220 feet, Pushed Halliburton plug down with drill pipe to 220 feet from surface. Put in 15 sacks of cement. Filled hole with heavy drilling mud to 35 feet of surface and set Halliburton plug at 35 feet dumped 10 sacks of cement on top.

"CORRECTED COPY"

APR - 2 1951
CO. 04-02-1951/6N
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to.....**Darby & Bothwell, Inc.**
Address.....**612 Orpheum Building, Wichita (2), Kansas**

STATE OF.....**Kansas**....., COUNTY OF.....**Sedgwick**....., ss.
.....**R.A. Bothwell**.....(employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature).....*R.A. Bothwell*
.....**612 Orpheum Building, Wichita, Kansas**
(Address)

SUBSCRIBED AND SWORN to before me this.....**31st**.....day of.....**March 1951**....., 19.....
J.P. Kendrick
.....**Notary Public.**

My commission expires.....**October 4, 1952**



23-13-17W
69-39

CORRECTED COPY

DRILLING LOG RECORD

Darby & Bothwell, Inc.
#1 Rome
SE SE SW Section 23-13-17W
Ellis County, Kansas

Casing Record

8 5/8" at 230 feet with 200 sacks
cement and 2 sacks C.C.

Commenced March 11, 1951
Completed March 24, 1951
Contractor Iron Drilling Co.

DRILLERS LOG

100 clay
140 sand
230 blue shale
605 shale & sand
830 sand
1178 red rock
1215 anhydrite
1550 shale
1800 shale & salt
1865 shale & shells
1982 lime
2140 shale & lime
2220 lime
2970 shale & lime
3220 lime
3340 shale & lime
3466 lime
3495 lime & shale
3560 cherty conglomerate
3566 Arbuckle dolomite

T.D. 3566

Sample & Drilling time Tops

Hebner 3220
Lansing 3266
Cherty Cong 3511
Arbuckle 3560

T.D. 3566

D.S.T. 3324-40, open 30 minutes,
recovered 60 feet oil & gas cut
mud (Est 25%)
B.H.P. 400# in 10 minutes

D.S.T. 3414-66, open 1 hour, recovered
110 feet very slightly oil cut
mud. B.H.P. 43# in 10 minutes

State of Kansas)
County Of Sedgwick) ss.

0460-1951

R.A.Bothwell, being first duly sworn on oath says the above is a true copy
of the drillers log and the sample tops of formations.

R.A.Bothwell
R.A.Bothwell

Subscribed and Sworn to before me this 31st day of March, 1951

J.P. Hendrick
Notary Public

23 13 17W
69 34
My Commission expires October 4, 1951