

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Locate well correctly on above
Section Plat

Ellis County. Sec. 23 Twp. 13 Rge. 17 (E) (W)
Location as "NE/CNW/SW" or footage from lines SE SW SW
Lease Owner Murfin Drilling Company
Lease Name Rome A#11 Well No.
Office Address Russell, Kansas 67665
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 8/16/73 19
Plugging completed 8/17/73 19
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey
Producing formation Depth to top Bottom Total Depth of Well 3615 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS


CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	167	none
				5 1/2"	3613	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Squeezed down 5 1/2" casing with 20 sacks gel, released plug and pumped 80 sacks cement.

PLUGGING COMPLETE.



(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KELSO CASING PULLING
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE
R. DARRELL KELSO (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS

SUBSCRIBED AND SWORN TO before me this 28th day of August 1973

My commission expires
MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

Margaret Melcher
Notary Public.

15-051-19359-00-00
WELL LOG

COMPANY **Murfin Drilling Company**
FARM **Rome "A"** NO. **11**

SEC. **23** T. **13S** R. **17W**
LOC. **SE SW SW**

TOTAL DEPTH **3615'**

COMM. **1-26-59**

SHOT OR TREATED

CONTRACTOR

ISSUED

Murfin Drilling Company


COMP.

2-4-59

RECEIVED
STATE CORPORATION COMMISSION

AUG 15 1973
08-15-1973
CONSERVATION DIVISION
Wichita, Kansas

COUNTY **Ellis**
KANSAS



CASING

20
15
12
13

10

8 **5/8" @ 167' w/155 sxs.**

6

5 **1/2" @ 3613' w/75 sxs.**

ELEVATION

1967' K. B.

1962' G. L.

PRODUCTION

66 BOPD

FIGURES INDICATE BOTTOM OF FORMATIONS

167 Surface Hole
350 Shale & Shells
560 Shale - Sand - Shells
640 Shale & Shells
820 Sand
1178 Red Bed & Shale
1216 Anhydrite - Lime
1555 Red Rock - Shale - Shells
1720 Shale & Shells
1835 Salt - Shale
2035 Shale - Lime Shells
3325 Lime - Shale
3405 Lime
3530 Lime - Shale
3615 Arbuckle

GEOLOGICAL TOPS:

Topeka	2948
Heebner	3212
Toronto	3232
Lansing-Kansas City	3260
Base Kansas City	3456
Arbuckle	3529

DST #1 3320-56

Open 2 hrs. Rec. 710' gas & 130' muddy oil. IF 0#. FF 0#. BHP 155# 20 min.

DST #2 3532-40

Open 1 hr. Rec. 15' oil cut mud & 15' mud. IF 0#. FF 0#. BHP 145# 20 min.

DST #3 3540-55

Open 1 hr. Rec. 55' heavily oil cut mud. IF & FF 0#. BHP 155# / 20 min.

DST #4 3561-86

Open 1 hr. Rec. 12' mud. IF 0#. FF 0#. BHP 485# / 20 min.