


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ellis County, Sec. 23 Twp. 13 Rge. 17 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NE SW SW
Lease Owner Murfin Drilling Company
Lease Name Rome A Well No. 14
Office Address 617 Union Center, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 18, 1960 19
Application for plugging filed " 19
Application for plugging approved " 19
Plugging commenced " 19
Plugging completed " 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3584 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1183'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Layed down drill pipe. Set first plug @550'. Displaced
20 sks. cement thru D. P. Set second plug @180'. Displaced
15 sks. thru drill pipe. Set top plug @40' with 1/2 sack hulls -
10 sks. cement. By Mr. Petty.

FEB 23 1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Murfin Drilling Company
Address _____

STATE OF Kansas, COUNTY OF Sedgwick, ss.
W. R. Murfin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) WR Murfin
(Address) _____

SUBSCRIBED AND SWORN TO before me this 18th day of February, 19 60

Alice Morrison
Notary Public.

My commission expires 11-19-63



WELL LOG 15-051-04130-00-00

COMPANY **Murfin Drilling Company**

SEC. 23 T. 13 R. 17

FARM **Rome**

NO. **14**

LOC. **NE SW SW**

TOTAL DEPTH **3584**

COUNTY **Ellis
KANSAS**


COMM. **1-9-60**

COMP. **1-18-60**

SHOT OR TREATED

CONTRACTOR **Murfin Drilling Company**

ISSUED



CASING

20	10	
15	8	5/8" w/525 sks.
12	6	
13	5	

ELEVATION **1974 KB**

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

- 190 12 1/4" surface hole
- 190 Shale
- 419 Shale-Shells
- 635 Sand-Shale-Shells
- 820 Sand
- 880 Red Bed
- 1175 Red Bed
- 1183 Anhy.
- 1215 Anhy.
- 1630 Shale-Shells
- 1720 Salt-Shale
- 1865 Shale-Lime Shells
- 3090 Lime-Shale
- 3220 Lime
- 3275 Lime-Shale
- 3470 Lime
- 3535 Lime & Shale
- 3546 Lime
- 3584 Lime "Arb"
- 3584 T.D.

Geological Tops:

Heebner	3225-1251
Toronto	3246-1272
Lansing	3272-1298
Cong.	3505-1531
Arb.	3524-1550

DST #1 -- 3332-67. Tool open 2 hrs., weak to very weak blow thruout, recovered 90' gas, 20' slightly oil cut mud, 15' drilling mud, IFP 0#, BHP 0#/20 min.

DST #2 -- 3521-46. Tool open 1 hr., weak blow for 9 min., recovered 10' mud, IFP 0#, FFP 0#, BHP 140#/20 min.

DST #3 -- 3542-84. Tool open 1 hr., fair blow thruout, recovered 250' muddy salt water, IFP 0#, FFp 160#, BHP 730#/20 min.

RECEIVED
SHERMAN COUNTY CLERK

02-23-1960

State of Kansas }
County of Sedgwick } ss:

I, W. R. Murfin of the Murfin Drilling Company
upon oath state that the above and foregoing is a true and correct copy of the log of the Rome #14 well.

W R Murfin

Subscribed and sworn to before me this 18th day of February 19 60

My Commission Expires: 11-19-63

Alice Morrison
NOTARY PUBLIC