


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Clark County. Sec. 2 Twp. 34S Rge. 22W (E) (W)  
Location as "NE/CNW/SE/SW" or footage from lines. SE Corner  
Lease Owner Graham-Michaelis Corporation  
Lease Name McMinimy Well No. 1-2  
Office Address P. O. Box 769, Woodward, Oklahoma 73801  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 10-5-73 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 10-17-73 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well \_\_\_\_\_  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5479' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				4 1/2	5478'	4726'
				8 5/8	582	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Spotted 25 sacks cement displaced by pump method with 9.5 mud. Shot pipe at 4726'.  
Spotted 35 sacks cement displaced with mud by pump method from 532 to 632'. Capped  
surface pipe with 15 sacks cement 3' to 45'.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 29 1973  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lillard Casing Pulling, Inc.  
Address P. O. Box 962, Woodward, Oklahoma 73801

STATE OF Oklahoma, COUNTY OF Woodward, ss.  
Lowell Lillard (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lowell Lillard  
Box 962, Woodward, Oklahoma  
(Address)

SUBSCRIBED AND SWORN TO before me this 26<sup>th</sup> day of Oct., 1973

My commission expires 1-11-76  
Lindie Lillard Notary Public.

McMINIMY #1-2

WELL RECORD:

LOCATION:

SE Corner of Section 2-34S-22W  
Clark County, Kansas

Commenced: 8-19-64  
Completed: 9-5-64  
(Rotary)

CONTRACTOR:

Graham-Michaelis Drilling Co.  
Liberal Division  
P. O. Box 1294  
Liberal, Kansas

CASING RECORD:

18 Joints 8-5/8" 24# Casing  
Cemented w/100 sx Sunset

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 26 1973  
CONSERVATION DIVISION  
Wichita, Kansas

	<u>LOG</u>	
Sand & Red Bed	0 -	265
Red Bed	265 -	1931
Lime & Shale	1931 -	5133
Lime	5133 -	5162
Lime & Shale	5162 -	5390
Lime	5390 -	5451
Sand & Lime	5451 -	5479

5479' - Total Rotary Depth

The undersigned, Graham-Michaelis Drilling Company, Liberal Division, certifies that the above log is a true and correct copy of the formations encountered in drilling the above mentioned well, as taken from the Daily Drilling Report.

GRAHAM-MICHAELIS DRILLING COMPANY  
LIBERAL DIVISION

By   
H. R. Michaelis