


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Ellis County. Sec. 24 Twp. 13 Rge. (E) 17 (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SE NW  
Lease Owner The Carl Todd Drilling Company, et al  
Lease Name KUHN Well No. 1  
Office Address 404 KFH Building, Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed May 27, 19 52  
Application for plugging filed June 4, 19 52  
Application for plugging approved May 29, 19 52  
Plugging commenced May 27, 19 52  
Plugging completed May 27, 19 52  
Reason for abandonment of well or producing formation Dry hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes, by telephone

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Box 326, Hays, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 3654 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	229	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 210'. Set plug, cemented with 15 sacks cement through drill pipe. Filled hole with mud to 40'. Set plug and cemented with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor The Carl Todd Drilling Company  
Address 404 KFH Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Carl Todd (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Carl Todd

404 KFH Building, Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 4th day of June, 19 52

My commission expires Feb. 8, 19 56

23-8390-s 6-51-20M

PLUGGING  
FILE SEC 24 13 R170  
BOOK PAGE 19 LINE 26

06-05-1952

Notary Public.

THE CARL TODD DRILLING COMPANY  
404 KFH BUILDING  
WICHITA 2, KANSAS

The Carl Todd Drilling Company, et al  
KUBIN No. 1  
SE SE NW 24-135-17  
Ellis County, Kansas

Elevation: 2004 R.B.  
Date Commenced: May 15, 1952  
Date Completed: May 27, 1952

Casing Record:

3-5/8" casing cemented at 229'  
with 145 sacks cement

Rotary Tools: 0' to 3654'

LOG

0	95	Surface clay, shale
95	310	Shale, shells
310	380	Shale, sand (streaks)
380	500	Shale, shells
500	520	Sand, iron
520	660	Shale
660	810	Sand, shale
810	925	Shale, shells, sand
925	1160	Red bed, shale, shells
1160	1198	Anhydrite
1198	1360	Shale, shells
1360	1500	Shale, salt
1500	1605	Shale, shells
1605	1810	Shale, lime shells
1810	2110	Lime, shale
2110	2205	Lime
2205	2480	Lime, shale
2480	2580	Shale, lime (streaks)
2580	3043	Shale, lime
3043	3240	Lime
3240	3288	Lime, shale
3288	3558	Lime
3558	3646	Conglomerate
3646	3654	Arbuckle

FOUNDATION TOPS - R.B.

Heebner . . . . .	3236
Lansing . . . . .	3287
Base Kansas City . . . . .	3514
Conglomerate . . . . .	3546
Arbuckle . . . . .	3646

I, Carl Todd, do hereby certify that  
the above log is correct to the best  
of my knowledge and belief.

Carl Todd

**PLUGGING**  
FILE SEC. 24T-135-170  
BOOK PAGE 19 LINE 26

**RECEIVED**  
STATE CORPORATION COMMISSION  
JUN 5 - 1952  
05-05-1952  
CONSERVATION DIVISION  
Wichita, Kansas