

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-25214-00-00
Spot: NWNWSESW Sec/Twnshp/Rge: 15-13S-17W
1275 feet from S Section Line, 1400 feet from W Section Line
Lease/Unit Name: T DREILING Well Number: 1
County: ELLIS Total Vertical Depth: 3640 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: PO BOX 352 370 W WICHITA AVE
RUSSELL, KS 67665

Surface Casing Size: 8.625 feet: 224

Well Type: DH UIC Docket No: Date/Time to Plug: 08/23/2003 12:00 PM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Order 225 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE BASYE WitnessType: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 08/24/2003 5:45 AM KCC Agent: BRUCE BASYE

Actual Plugging Report:

1st. Plug at 3500' w/25 sxs.
2nd. Plug at 1250' w/25 sxs.
3rd. Plug at 730' w/100 sxs.
4th. Plug at 275' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

RECEIVED
AUG 26 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Bruce Basye
(TECHNICIAN)

INVOICED

DATE 9-2-03

2004060444

AUG 25 2003