

3

4-4

313

6 070911

API NUMBER 15- 051-24,700-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
206 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SE SE SE, SEC. 19, T 13 S, R 16 W/E

330 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7064

Lease Name Dreiling Well # 2

Operator: Cattlemans Oil Op

County Ellis 114.04

Name & Address HC 39 Box 74

Well Total Depth 3509 feet

Hays, Ks. 67601

Conductor Pipe: Size 0 feet

Leo R. Dorzweiler

Surface Casing: Size 8 5/8 feet 249

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cement Co Tools License Number

Address Russell, Ks. Hays, Ks.

Company to plug at: Hour: Am Day: 4th Month: April Year: 19 91

Plugging proposal received from Leo Dorzweiler

(company name) Cattlemans Oil Operations (phone)

were: 8 5/8 249 ft. s.p. cwc w/150 sks cement; 5 1/2 casing at 3500 ft. w/125 sks cement. Perfs 3492 - 96 at bottom sand to 3400 ft. and w/5 sks cement. Shot casing at 2260 ft. recovered 2260 ft. of 5 1/2 casing. Proposal 300 sks 60/40 poz 8% gel and 5 sks hulls. Run 2 3/8 tubing to 1142 ft. (any) Circ cement to surf.

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 1:00AM Day: 4 Month: April Year: 19 91

ACTUAL PLUGGING REPORT Cattlemans Oil ordered 300 sks 60/40 poz 8% gel and

5 sks hulls. Spotted and displaced cement through tubing.

1. Ran 2 3/8 tubing to 1142 fr. w/250 sks cement.

2. 2 3/8 tubing at 600 ft. cwc w/48 sks cement. Cement received

Total cement 298 sks cement. Cemented by Allied Cement.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED (did not observe this plugging.)

DATE 4-29-91

W.M. NO. 31686

Gib. S.

Signed Marion J. Schmidt (TECHNICIAN)

APR 22 1991 04-22-1991