

6 070912

4-4
API NUMBER 15-

051-01378-00264
3-5-45

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C S/2 SE SESEC. 19, T 13 S, R 16 W&E

660 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7064

Lease Name Dreiling Well # 1

Operator: Cattlemans Oil Operations

County Ellis 113.52

Name & Address HC 39 Box 74

Well Total Depth 3493 feet

Hays, Ks. 67601

Conductor Pipe: Size 0 feet

Leo R. Dorzweiler

Surface Casing: Size 8 5/8 feet 1123 ft.

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing Co. Tools License Number

Address Russell, Ks. Hays, Ks.

Company to plug at: Hour: AM Day: 4 Month: April Year: 19 91

Plugging proposal received from Leo R. Dorzweiler

(company name) Cattlemans Oil Operations (phone)

were: 8 5/8 - 1123 ft. s.p. cwc w/425 sks cement. 5 1/2 casing set at 3489

w/100 sks cement. Perfs at 3458 - 3284 at bottom sand to 3200 ft. and w/

5 sks cement. Shot casing at 2440. Recovered 2440 ft. of 5 1/2 casing.

Proposal 250 sks 60/40 poz 8% gel and 5 sks hulls. Pump in 8 5/8

casing w/pump truck w/5 sks hulls added shut in under pressure.

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:30PM Day: 4 Month: April Year: 19 91

ACTUAL PLUGGING REPORT Cattlemans Oil ordered 250 sks

60/40 poz 8% gel and 5 sks hulls. Pmped in 8 5/8 casing w/pump truck.

Pumped in 8 5/8 s.p. w/250 sks cement w/1 sk hulls added.

Max pressure 800 psig. Shut in at 400 psig. Cemented by allied

cement. Russell.

RECEIVED
STATE CORPORATION COMMISSION
04-22-1991
APR 22 1991

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-29-91
W.M. NO. 31685

Lib. S.

Signed Marion J. Schmidt (TECHNICIAN)