

4-071178

TO: .
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-051-24,925-00-00
NW SE SE /4 SEC. 19, 13 S, 16 W
990 feet from S section line
990 feet from E section line

6-17

Operator license# 5252 Lease: Brungardt F Well # 1
Operator: R.P. Nixon Operations, Inc. County: Ellis
Address: 207 West 12th Street Well total depth 3553 ^{115.47} feet
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet
Paul Nixon Surface pipe 8 5/8 Inch @ 209 feet

Aband. oil well X, Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: Allied Cementing Company - Co Tools License# _____

Address: Russell, Kansas 67665 - Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 17 Month: June Year: 1996

Plugging proposal received from: Paul Nixon

Company: R.P. Nixon Operations, Inc. Phone: _____

Were: 8 5/8" - 209' S.P. cwc. w/140 sxs cement. 5 1/2" casing set at 3551' w/100 sxs cement. Elv. 1983' - Anhydrite 1123' - Casing Good. Arbruckle 3499' - Pipe set 5-28-96. Proposal by Herb Deines - 235 sxs 60/40 pozmix - 10% gel and 5 sxs hulls. Plug well through 5 1/2" casing - will pull casing out of hole. 1) Sand bottom 50' above perfs - then 5 sxs cement. 2) 120 sxs w/2 sxs hulls at 1725'. 3) 30 sxs at 1150' with 1 sack of hulls. 4) 30 sxs at 550' with 1 sack of hulls. 5) 35 sxs at 175' and 20 sxs on top.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 7:00 P.M., Day: 17, Month: June, Year: 1996

Actual plugging report: Nixon Operations ordered 235 sxs 60/40 pozmix - 10% gel - 5 sxs hulls. Pumped cement in with pump truck. Spotted and displaced all cement through casing while pulling 5 1/2" casing out of hole.

- 1) Sand bottom to 3440' - then 5 sxs cement to 3400'.
- 2) Shot casing at 2500' and 2740' - recovered 2740' of casing.
- 3) Spotted 120 sxs cement with 2 sxs hulls at 1700'.
- 4) Spotted 30 sxs with 1 sack of hulls at 1140'.
- 5) Spotted 30 sxs with 1 sack hulls at 540'.
- 6) Spotted 35 sxs with 1 sack hulls at 175' - Cement circulated.

Remarks: Cemented by Allied Cementing.

Condition of casing(in hole): GOOD X BAD _____ Anhy.plug: YES _____ NO X
Bottom plug(in place): YES X, CALC _____, NO _____ Dakota plug: YES X, NO _____
Plugged through TUBING _____, CASING X. Elevation: 1983 GL

I did[X] / did not[] observe the plugging.

Marion Schmidt
(agent)

NOTICED
DATE JUN 26 1996
NO. 45884
6-17

RECEIVED
CORPORATION COMMISSION
JUN 25 1996
CONSERVATION DIVISION
WICHITA, KS