

15-051-22012-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- \_\_\_\_\_

NW, Sec. 35, T 13 S, R 16 WE

\_\_\_\_\_ feet from N/S section line

\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5267

Lease Name Brungardt 'B' Well # 1

Operator: K & E Petroleum, Inc.  
Name &  
Address Hardage Center, Suite 300, 100 S. Main  
Wichita, Ks. 67202

County Ellis

Well Total Depth 3520 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8" feet 318'

Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelao Casing Pulling License Number 6050

Address P.O. Box 176, Chase, Ks. 67524

Company to plug at: Hour: 1:30 PM Day: 28 Month: 10 Year: 19 82

VERBAL PLUGGING ORDERS GIVEN TO Millard Kelao

(company name) Kelao Casing Pulling (phone) 316-938-2457

were: Order 165 sacks 5/8 pozmix - 4 1/2" Sel. - 3 1/2" Cal. Cl., 5 sacks hulla, 20 sacks Sel. & 9 5/8" plug.

Signed Glenn L. Schell  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:45 PM Day: 28 Month: 10 Year: 19 82

ACTUAL PLUGGING REPORT 8 5/8" - 318' W/commen. 4 1/2" set at 3464' w/150 sacks.

Plugged back to 3422'. Top perf. at 3203'. Plugged bottom w/sand, 5 sacks cement on bottom + 5 sacks on top of sand. Shot pipe 1 time + recovered 2606'. Pumped in 8 5/8", 25 sacks cement, 4 hulla, 15 sacks Sel., 70 sacks cement, 5 sacks Sel., 1 sack hulla, released plug & followed w/70 sacks cement.

Maximum pressure 700 pounds.

Remarks: \_\_\_\_\_

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 08 1982  
CONSERVATION DIVISION  
Wichita, Kansas  
11-08-1982

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

Signed Glenn L. Schell  
(TECHNICIAN)

INVOICED  
11-23-82  
1684-W