

To: 1 040520
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

2-25

API NUMBER 15- 007-20,327 0000
C NW SE, SEC. 11, T 35 S, R 13 WXE
1980 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5363
Operator: Berexco
Name & Address Box 723
Hays, KS 67601

Lease Name Achenbach C Well # 1
County Barber 159.28
Well Total Depth 4901 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 253

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____
Plugging Contractor Clarke Corporation License Number 5105
Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 5:15 p.m. Day: 25 Month: 2 Year: 19 91

Plugging proposal received from Jeff Clarke
(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4901' w/100 sx cement. Perfs at 4883-86, 4849-56'
1st plug sand back to 4800' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,
release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____
Operations Completed: Hour: 6 p.m. Day: 25 Month: 2 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped down 4 1/2" casing with 30 sx common cement;
stopped plug at 4000'
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.
Maximum pressure 400 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2700' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 3-8-91
INV. NO. 31072

Signed Stephen J. Pfeifer
(TECHNICIAN)