

To: 1 040519
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

2-25
API NUMBER 15- 007-20,942 0000
N/2 N/2 NE, SEC. 11, T 35 S, R 13 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363

Operator: Berexco
Name & Address Box 723
Hays, KS 67601

4950 feet from S section line

1320 feet from E section line

Lease Name Achenbach A Well # 5

County Barber 160.74

Well Total Depth 4946 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 415

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 4 p.m. Day: 25 Month: 2 Year: 19 91

Plugging proposal received from Jeff Clarke

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 4940' w/250 sx cement. Perfs at 4935-42

1st plug sand back to 4870' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,
release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:45 p.m. Day: 25 Month: 2 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4880' and dumped 5 sx cement on top of
sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 400 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 3200' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOLVED

DATE 3-8-91

INV. NO. 31068

Signed Stephen J. Pfeifer
(TECHNICIAN)