

To: 1 040517
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363

Operator: Berexco
Name & Address: Box 723
Hays, KS 67601

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☐

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 12:15 p.m. Day: 25 Month: 2 Year: 19 91

Plugging proposal received from Jeff Clarke

(company name) Clarke Corporation (phone) 316-886-5665

were: 4½" at 4839' w/100 sx cement, Casing collapsed at 1000'

1st plug pump 10 sx cement and water, circulate,

2nd plug pump 50 sx common cement to bottom,

3rd plug pump 200 lbs. hulls and 200 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 1 p.m. Day: 25 Month: 2 Year: 19 91

ACTUAL PLUGGING REPORT Unable to sand back perms. Couldn't get bailer below 1000' due to collapsed casing.

1st plug pumped down 4½" with 50 sx common cement, cement circulated out 8 5/8" X 4½"

annulus. Stopped pumping, left 10 sx cement in 4½" casing at 938',

2nd plug pumped down 8 5/8" surface pipe with 200 lbs. hulls and 200 sx cement.

Maximum pressure 600 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 600' of 4½" casing.
(If additional description is necessary, use BACK of this form.)

INVOLVED (If additional description is necessary, use BACK of this form.) observe this plugging.

DATE 3-8-91

WV. NO. 31069

Signed *Stephen J. Pfeifer*
(TECHNICIAN)