

To: 1 040516  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

2-25 15-007-3039-000  
API NUMBER 15 Drilled 5/5/75  
C NW NW, SEC. 12, T 35 S, R 13 W/R1  
4620 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363  
Operator: Berexco  
Name & Address Box 723  
Hays, KS 67601

Lease Name Achenbach Well # 2  
County Barber 159.93  
Well Total Depth 4921 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 256

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105  
Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 2 p.m. Day: 25 Month: 2 Year: 19 91

Plugging proposal received from Jeff Clarke

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 4911' w/100 sx cement, Perfs at 4854-62, squeezed w/150 sx cement, 4878-79'

1st plug sand back to 4825' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release  
8 5/8" wiper plug and pump 100 sx cement.

DATE OF PLUGGING \_\_\_\_\_

Plugging Proposal Received by Steve Pfeiffer 8 1001  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3 p.m. Day: 25 Month: 2 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4825' and dumped 5 sx cement on top of  
sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 300 psi and shut in 250 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 3000' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 3-8-91

INV. NO. 31070

Signed Stephen J. Pfeiffer  
(TECHNICIAN)