

To: 1 040518
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

2-25
API NUMBER 15- 007-20,268 -5000
C SE NW, SEC. 12, T 35 S, R 13 W/E
3300 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363
Operator: Berexco
Name & Address: Box 723
Hays, KS 67601

Lease Name Achenbach Well # 1
County Barber 158.76
Well Total Depth 4885 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 215

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105
Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 9:15 a.m. Day: 25 Month: 2 Year: 19 91

Plugging proposal received from Jeff Clarke
(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4884' w/100 sx cement. Perfs at 4850-78'
4 1/2" casing at sometime had been squeezed and cement circulated to surface and backside of
4 1/2" casing.

1st plug pump down 4 1/2" casing with 200 lbs. hulls and 33 sx cement,

2nd plug pump into 8 5/8" X 4 1/2" annulus with 2 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN) FEB 28 1991

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 a.m. Day: 25 Month: 2 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped down 4 1/2" casing with 200 lbs. hulls and 33 sx cement,
Maximum pressure 1050 psi and shut in 420 psi.

2nd plug pumped into 8 5/8" X 4 1/2" annulus with 2 sx cement. Pressured up to 1050 psi and
shut in 700 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 3-8-91
INV. NO. 31071

Signed Stephen J. Pfeifer (TECHNICIAN)
FORM CP-2/3 Rev. 01-84