

6 060168

15-051-23396-00-0

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15

NW, SEC. 8, T. 13 S., R. 17 W.
330 feet from N1/8 section line

2310 feet from W1/8 section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7064

Lease Name Poliska F Well # 1

Operator: Cattleman's Oil Operations

County Ellis

Name & Address Catherine Route, Box 32,

Well Total Depth 3610' 117.33 feet

Hays, Ks. 67601

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 207'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 176, Chase, Ks. 67524

Company to plug at: Hour: 10:00 AM Day: 7 Month: March Year: 19 84

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: Order 165 lbs. 50 pos mix - 6 1/2 gal. Gel - 3% lat. U., 20 lbs. Gel, 5 lbs. hulla & 8 5/8" plug.

Plugging Proposal Received by John G. Schell (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:45 PM Day: 7 Month: March Year: 19 84

ACTUAL PLUGGING REPORT 8 5/8" - 207' unc. 5 1/2" set at 3610' w/ 125 lbs.

Plug back to 3431'. Plugged bottom w/ 5 lbs. cement, sand & 5 lbs. cement to 3275' w/ Top reef at 3330'. Shot pipe 2 times & recovered 2540'. Pumped in 8 5/8" - 4 lbs. hulla, 25 lbs. cement, 15 lbs. Gel, 70 lbs. cement, 5 lbs. Gel, 1 lb. hulla, released plug & followed w/ 70 lbs. cement w/ 800 pounds pressure.

Remarks: By Sun

RECEIVED STATE CORPORATION COMMISSION

MAR 19 1984

I (did not) observe this plugging.

DATE 3-21-84

CONSERVATION DIVISION Wichita, Kansas

John G. Schell (TECHNICIAN)

INV. NO. 0818