


15-007-01035-00-06

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barber County. Sec. 22 Twp. 833S Rge. (E) 14 (W)
Location as "NE/CNWSW" or footage from lines C SW SW
Lease Owner Sunray Mid-Continent Oil Company
Lease Name Harbaugh 'A' Well No. 1
Office Address Box # 788, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Dec. 22 19 58
Application for plugging filed Dec. 23, 19 58
Application for plugging approved Dec. 24, 19 58
Plugging commenced Dec. 22, 19 58
Plugging completed Dec. 22, 19 58
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp
Producing formation Depth to top Bottom Total Depth of Well 4685 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13-3/8"	110'	None
				8-5/8"	1015'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole w/mud to 240', set plug w/ 1/3 sack
hulls, wood plug and 20 sacks Pozmixcement.
Filled hole w/mud to 35', 1/2 sack hulls, wood plug,
and 15 sacks cement. Plugging completed.

Log attached.

RECEIVED
STATE CORPORATION COMMISSION
JAN 7 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Halliburton Oil Well Cementing Co.
Address

STATE OF KANSAS, COUNTY OF BARTON, ss.
N. E. Montgomery (employee of owner) or (owner or operator) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.

(Signature) N. E. Montgomery

Box # 788, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 6 day of January, 19 59

My commission expires Dec. 24, 1960

Notary Public.

PLUGGING
FILE SEC 22T 33 R14W
BOOK PAGE 6 LINE 10

Sunray Mid-Continent Oil Company
Tulsa, Oklahoma

Tulsa, Oklahoma
December 24, 1958

CONTRACTOR: Stickle Drilling Company
Drilling Commenced: December 5, 1958
Drilling Completed: December 22, 1958

Harbaugh A-1 NE SW SW Sec-
tion 22-33S-14W, Barber Co.
Kansas.

DRILLERS LOG

Depth Figures indicate base of formation:

Surface	0
Shale & Sand	110
Sand & Gravel	300
Red Bed - Shale & Shells	558
Red Bed & Shells	815
Red Bed Shale & Shells	955
Shale & Shells	1017
Shale & Lime	1230
Shale & Shells	1570
Shale & Anhydrite Shell	1620
Shale & Shells	1810
Shale & Shells & Lime	1975
Lime & Shale	2290
Lime	2410
Shale	2420
Lime & Shale	2615
Shale & Lime	2725
Lime & Shale	2859
Shale & Lime	3215
Shale	3375
Shale & Lime	3715
Lime	3810
Lime & Shale	4300
Lime	4630
Mississippi	4685 TD

RECEIVED
STATE COMMISSIONER OF GEOL. & NAT. RES.
JAN 7 1959
CONSERVATION DIVISION
Wichita, Kansas

I, Fred E. Stickle hereby certify the above to be a true and complete
Drillers Log of Sunray Mid-Continent Oil Company's Harbaugh A-1 NE SW
SW Section 22-33S-14W, Barber County, Kansas.

Fred E. Stickle
Fred E. Stickle

Lillian T. Bonham
Notary Public

February 13, 1960
My Commission Expires

PLUGGING
FILE SEC. 22-T 33 R 14W
BOOK PAGE 6 LINE 10