

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-051 23,169-00-00

LEASE NAME Polifka B

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

990 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 13 TWP. 13 RGE. 18 (X) or (W)

COUNTY Ellis

Date Well Completed 1982

Plugging Commenced 8-21-98

Plugging Completed 8-21-98

LEASE OPERATOR D Oil, Inc.

ADDRESS P. O. Box 278 Victoria, Ks.

PHONE# (785) 735 9225 OPERATORS LICENSE NO. 9394

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7-31-98 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation LKC Depth to Top 3500 Bottom 3550 T.D. 3763

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface	- 0 -	167	8 5/8	167	None
	Production	- 0 -	3762	5 1/2	3762	None

RECEIVED
KANSAS CORPORATION
1998 SEP 13 10 15 AM

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Pump down 5 1/2 casing 40 sks. 60-40 Poz. and 150# Hulls. Pump 20 sks. Get and 350# hulls.

Pump and squeeze with 125 sks 60-40 Poz. at Max. 1,600# P.S.I. SIP 500#. Back side cement visible.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. _____

Address _____

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: D Oil, Inc.

STATE OF Kansas COUNTY OF m Ellis, ss.

Alfred J. Dreiling


(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Victoria, Ks

SUBSCRIBED AND SWORN TO before me this 1ST day of SEPTEMBER, 19 98



[Signature] Notary Public

My Commission Expires: NOVEMBER 14, 1998