

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-051-05807-00-01

API NUMBER 15 - D - 900

LEASE NAME Bemis

WELL NUMBER 6

1650 Ft. from S Section 11

4290 Ft. from E Section 11

SEC. 22 TWP. 11 RGE. 17 (E) of 11

COUNTY Ellis

Date Well Completed 5-26-37

Plugging Commenced 1-23-91

Plugging Completed 2-5-91

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Helmerich & Payne, Inc.

ADDRESS P.O. Box 558 Garden City, Kansas 67846

PHONE# (316) 276-3693 OPERATORS LICENSE NO. 5293

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays (Don Butcher on location)

Is ACO-1 filed? If not, is well log attached? N/A

Producing Formation Arbuckle Depth to Top 3419 Bottom 3430 T.D. 3970

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put in	Pulled out
		0	139	16"	139	0
		0	1143	10 3/4"	1143	0
		0	3419	7"	3419	0
		3390	3563	5 1/2"	173	0

MAY 09 1991

CONSERVATION DIVISION  
Wichita Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging materials were used, state the character of same and depth placed, from feet to feet each set.

Cleaned out 7" csg. to 331'. Could go no deeper. Hook up to 7" csg and pump 100 sks Class A cement followed by 300 sks 65/35 Poz, 8% gel, 1/2 #/sk floccle w/500# hulls in last 100 sks cmt.

Staged cmt for 2 hours No squeeze pressure Pump 450 sks 65/35 poz 10% gel w/1/2 #/sk floccle at 2 BPM @ 100#. Start pump move cmt and well pressured to 300#. Job complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No.

Address Hays, Kansas

STATE OF Kansas COUNTY OF Ellis, ss.

Ken Jehlik

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed with the same are true and correct, so help me God.

(Signature) *Ken Jehlik*

(Address) Box 558 Garden City, Kansas 67846

NOTARY PUBLIC - State of Kansas  
JUDY S. RICHMEIER  
My Appt. Exp. 8-15-92

SUBSCRIBED AND SWORN TO before me this 8th day of May, 1991

*Judy S. Richmeier*  
Notary Public

My Commission Expires: August 15, 1992