


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Ellis County, Sec. 22 Twp. 11S Rge. 17 (E) (W)
Location as "NE/CNW/SW" or footage from lines SW/4 NW/SW/SW
Lease Owner Toland and Reeves
Lease Name F.A. Bemis Well No. #3
Office Address Box 4336, Oklahoma City, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed Yes 19____
Application for plugging approved Yes 19____
Plugging commenced _____ 4-19 1957
Plugging completed _____ 5-10 1957
Reason for abandonment of well or producing formation _____
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3426' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				7"		1,633'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Measured into TD 3426'.
Plugging started 4-19-57. Finished 5-10-57.
Plugged off bottom with sand to 3410' and dumped 5 sacks cement with bailer.
Shot 7" casing at 1,633'. Pulled pipe out of hole and plugged well with heavy mud to 500' and set permanent rock bridge. Dumped 30 sacks cement.
Filled hole with heavy mud to 35' and mixed 15 sacks for cap on well.

RECEIVED
STATE CORPORATION COMMISSION
MAY 16 1957 05-16-57
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co.
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J.O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J O Forbes
Box 221, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 15th day of May, 1957.

Betty S. Edman
Notary Public.

My commission expires November 8, 1960.

PLUGGING
FILE SEC 22 T 11 R 17W
BOOK PAGE 47 LINE 9

WELL RECORD

15-051-03363-0000

British American Oil Producing Co.

Located: SW/4 of Section 22-11S-17W,

F. A. Bemis No. 3

Ellis County, Kansas

NW-SW-SW

	From	To
Shale & shells	0	90
Lime	90	93
Shale & shells	93	215
Sand	215	580
Shale	580	690
Sand	690	710
Red bed	710	920
Sand	920	1005
Red bed & shale	1005	1105
Anhydrite	1105	1160
Shale	1160	1165
Shale & shells	1165	1375
Lime & shale	1375	1470
Salt	1470	1555
Shale	1555	1709
Lime	1709	1765
Shale & shells	1765	1850
Lime	1850	1865
Broken lime	1865	2040
Lime & shale	2040	2135
Shale to lime	2135	2195
Lime	2195	2285
Shale	2285	2300
Lime	2300	2418
Lime & shale	2418	2465
Lime	2465	2485
Broken lime & shale	2485	2560
Shale	2560	2633
Shale & shells	2633	2712
Sticky shale	2712	2745
Shale	2745	2790
Lime	2790	2805
Shale	2805	2875
Lime	2875	2915
Lime & shale	2915	2934
Shale	2934	2954
Lime	2954	3003
Lime & shale	3003	3190
Lime	3190	3290
Lime & shale	3290	3418
Siliceous lime	3418	3426
Total Depth	3426	

Drilling commenced Jan. 1, 1937
 Drilling completed Feb. 3, 1937

Elevation 1928'

First potential - 2309 bbls. on Feb. 6, 1937

CASING RECORD - 16" OD Set at 93' - cemented with 115 sacks
 10 3/4 " 1146' " " 437 "
 7" OD " 3421' " " 175 "

RECEIVED
 STATE CORPORATION COMMISSION

MAR 12 1937
 03-12-57
 CONSERVATION DIVISION
 Wichita, Kansas

WLP 5-14-37

PLUGGING
 FILE SEC 22 T 11 R 17W
 BOOK PAGE 147 LINE 9