


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Ellis County. Sec. 22 Twp. 11 Rge. 17X (E) (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines SE SW SW
Lease Owner Russell Supply Company
Lease Name Bemis Well No. 8
Office Address Box 25 Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 19
Application for plugging filed August 6, 1955 19
Application for plugging approved August 8, 1955 19
Plugging commenced August 12, 1955 19
Plugging completed August 20, 1955 19
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Arbuckle Depth to top 3160' Bottom 3424' Total Depth of Well 3432' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				7"	3424'	1814.82'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud and sand to 2500', dumped 5 sacks cement 2500'-2475'.
Pulled pipe to 1200', mixed and pumped 20 sacks mud into pipe, pulled pipe out. Bailed mud down to 300', put in 10' rock bridge to 290', mixed and run 25 sacks cement from 290'-240', filled hole with mud from 240' - 25', put in 5' rock bridge to 20', mixed and run 10 sacks cement to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Arnett Casing Pulling Company
Address Hoisington, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
J. L. King, Owner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. L. King
Russell, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 12 day of Sept, 19 55

My commission expires 10-15-57

Margaret McLean
Notary Public.

PLUGGING
FILE SEC 22 T 11 R 17W
BOOK PAGE 140 LINE 41

STATE CORPORATION COMMISSION
SEP 19 1955
CONSERVATION DIVISION

Jeff 15-051-03307-0000 *De*
 THE BRITISH-AMERICAN OIL PRODUCING COMPANY

PRESENT CONDITION	LOG	PROPOSED CONDITION	DEPTH
16", 70# LW • 139' w/150 sx		10 sx cement	139'
10 3/4" 100# LW • 1163' with 575 sx			1000' 1163'
Anhydrite 1161'			
		Mud	2000'
		Mud	
Topoka lime 2880'			
5 sx cement top of fish			3000'
Top 2912'			
K.O. Lansing 3160' Arbuckle 3124'			3160' 3124'
ID 3432' 6 1/4" Hole 7", 24# LW 3424' w/ 175 sx			4000'

PROGNOSIS

A. F. E. NO. _____ DATE 3-8-55
 STATE: Kansas COUNTY: Ellis
 DISTRICT: Central
 FIELD: Bonis
 WELL: Bonis #8
 LOCATION DESCRIPTION: SE SW SW, S22-118-17W

ELEVATION: 1959' DF

PROGRAM

1. Spot 10 sx of neat cement in top of 7" casing.
2. Spot 5 sx. of neat cement in top of 7" x 10 3/4" annulus

RECEIVED

PLUGGING
 FILE SEC 22 T 11 R 17W
 BOOK PAGE 140 LINE 41

09-10-95

Original Signed by *Wesley W. Moore*
 Fred Norris PROD. DEPT.

SUBMITTED BY: *D. E. Edstrom* ENGR. DEPT.
 COPIES: GEOL. DEPT.