


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Ellis County. Sec. 22 Twp. 11S Rge. 17W (E) (W)
Location as "NE/CNWSW" or footage from lines _____
Lease Owner Ormahd Industries
Lease Name Bemis A# 2A Well No. _____
Office Address Plainville, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 4/19/73 _____ 19____
Plugging completed 4/24/73 _____ 19____
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3400 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				15 1/2	108	none
				10 3/4	1095	none
				7"	3396	1690'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole, pushed plug to 3360' and set rock bridge. Mixed and dumped 6 sacks cement. Shot pipe at 2296', 2004', to 1697', pulled 54 joints. Set rock bridge at 365' and dumped 7 yards ready mix.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
APR 27 1973
CONSERVATION DIVISION
Wichita, Kansas
04-27-73

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KELSO CASING PULLING
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of April, 1973

My commission expires _____
MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975



Margaret Melcher
Notary Public.

15-051-05846-0001

BEMIS A - 2

SW NW NW 22-11-17W
Ellis County, Kansas

Shale & shells	0 - 85
Shale	85 - 140
Sand & shale	140 - 388
Shale & shells	388 - 550
Iron	550 - 572
Shale	572 - 576
Shale & shells	576 - 980
Shale & red bed	980 - 1089
Anhydrite	1089 - 1095
Lime	1095 - 1265
Shale & lime	1265 - 1324
Shale & shells	1324 - 1425
Shale	1425 - 1460
Salt & sand	1460 - 1701
Lime & shale	1701 - 1925
Lime	1925 - 2145
Shale	2145 - 2155
Lime	2155 - 2250
Sand & lime	2250 - 2300
Shale	2300 - 2430
Lime	2430 - 2460
Shale	2460 - 2490
Shale & shells	2490 - 2585
Shale	2585 - 2760
Lime	2760 - 2770
Shale	2770 - 2825
Lime	2825 - 3085
Lime & shale	3085 - 3150
Lime	3150 - 3360
Shale	3360 - 3384
Simpson shale	3384 - 3392
Simpson sand	3392 - 3396
Siliceous lime	3396 - 3473

RECEIVED
STATE CORPORATION COMMISSION
FEB 18 1969
CONSERVATION DIVISION
Wichita, Kansas