

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Ellis County, Sec. 22 Twp. 11 Rge. (E) 17 (W)

Location as "NE/CNWxSWx" or footage from lines NW/4 NE/4 NW/4
Lease Owner Ormand Industries
Lease Name Bemis "A" Well No. 4
Office Address 2118 Adolphus Tower, Dallas, Texas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed Sept. 21 19 37
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 5/2/69 19
Plugging completed 5/3/69 19
Reason for abandonment of well or producing formation depleted.

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey
Producing formation Arbuckle Depth to top 3423 Bottom 3460 Total Depth of Well 3460 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Arbuckle	oil	3423	3460	15 1/2"	34	none
				10"	1127	none
				7"	3424	1591'
				5 1/2" liner		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked bottom, ran sand to 3400', ran 5 sacks of cement. Loaded hole, shot pipe, pipe came loose, pulled 52 joints. Allied plugged well with 160 sacks of cement, 30 sacks gel and 5 sacks hulls.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
MAY 20 1969 05-20-69
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 6th day of May, 19 69

My commission expires 2/15/71

Margaret Melcher
Notary Public.

BEMIS A - 4

NW NE NW 22-11-17W
Ellis County, Kansas

Shale	0 - 32
Shale & shells	32 - 228
Sand, iron & shale	228 - 631
Shale & shells	631 - 845
Shale, shells & red beds	845 - 1127
Anhydrite lime	1127 - 1185
Red rock	1185 - 1225
Red beds & shale	1225 - 1350
Shale & shells	1350 - 1489
Shale & salt	1489 - 1607
Salt broken	1607 - 1640
Red rock & shells	1640 - 1693
Lime	1693 - 1793
Lime & shale	1793 - 1842
Shale & lime	1842 - 1945
Lime	1945 - 2028
Lime & shale	2028 - 2062
Lime	2062 - 2230
Lime & shale	2230 - 2300
Lime	2300 - 2347
Lime & shale	2347 - 2400
Lime	2400 - 2450
Lime & shale	2450 - 2505
Lime	2505 - 2545
Lime & shale	2545 - 2660
Shale & lime	2660 - 2694
Lime & shale	2694 - 2747
Lime	2747 - 2782
Lime & shale	2782 - 2844
Lime	2844 - 2953
Lime & shale	2953 - 2962
Lime	2962 - 3405
Lime & shale	3405 - 3423
Siliceous lime	3423 - 3460

RECEIVED
STATE CORPORATION COMMISSION
FEB 18 1969
CONSERVATION DIVISION
Wichita, Kansas