

15-051-21089-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

SEP 30 1975
09-30-1975
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name F & M Oil Co., Inc.

Complete Address 505 Union Center, Wichita, Kansas

Lease Name Wannamaker Well No. 1

Location NW SE SE Sec. 5 Twp. 13 Rge. (E) (W) 19

County Ellis Total Depth 3870'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Duke Drlg.

Address Great Bend, Kansas License No.

Operation Completed: Hour 1 P Day 28 Month 9 Year 1975

The above well was plugged as follows:

RTD 3870' 8 5/8 csg set 203' cwc 125 sk. Plg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 550' thru drill pipe.

Heavy mud to 185' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/30/75

INV. NO. 1984-11

Signed: [Signature]
Well Plugging Supervisor