

KANSAS

*Y*

STATE CORPORATION COMMISSION

15-051-20541-0000

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 15 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Woodman & Iannitti

Complete Address 706 Union Nat'l Bldg., Wichita, Kansas

Lease Name Mernis Well No. 1

Location SW SW SE Sec. 3 Twp. 13 Rge. (E) (W) 19

County Ellis Total Depth 378<sup>2</sup>

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated     

Plugging Contractor Co. Tools

Address      License No.     

Operation Completed: Hour 4:30A Day 14 Month 12 Year 1969

The above well was plugged as follows:

RTD 378<sup>2</sup> 8 5/8 csg set at 190' cwc 140 sk Cmt. Mat. 50-50 poz cmt W/6% total gel  
Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk cmt  
thru drill pipe. Heavy mud to 150' set cementing plug and displaced 20 sk cmt thru  
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base  
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo. P. Mason  
Well Plugging Supervisor

DATE 12/15/69  
INV. NO. 1049-W