

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-051-21,621-00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Thomason Oil Co.

Complete Address 27th. & Oak, Hays, Ks. 67601

Lease Name Holt Well No. 1

Location NE NE NE Sec. 16 Twp. 13 Rge. 19 (East) (West)

County Ellis Total Depth 3790'

Abandoned Oil Well XXX Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Ostrum Well Service Inc.

Address 1012 W. Mill, Box 368, Plainville, Ks. 67663 License No. 777

Operation Completed: Hour: 11:40 AM Day: 6 Month: Feb. Year: 19 82

Plugging Operations attended by Agent?: All XXX Part None

The above well was plugged as follows:

8 5/8" 200' S.P. cuc. W/200 sacks common. 4 1/2" Caseing set at 3790' with 200
sacks common. Plugged back to 3753'. Top perf. at 3136'. Set cast iron plug at
3100' with 1 sack cement on top. Shot pipe 2 times and recoverd 2150'. Ordered
140 sacks 50/50 posmix 4% Gel.-3% Cal.Cl., 19 sacks Gel., 5 sacks of hulls and
8 5/8" plug. Pumped into 8 5/8" S.P. with pump truck 4 sacks of hulls, 15 sacks
Gel., 70 sacks cement, 4 sacks Gel., 1 sack hulls, released plug and followed
with 70 sacks cement. Maximum Pressure 500 pounds.

Amount of Surface Casing: 200' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed:
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
FEB - 9 1982

CONSERVATION DIVISION
Wichita Kansas

INVOICED
DATE 2-12-82
INV. NO. 9398W