

KANSAS

FORM CP-3

Rev. 5-5-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

RECEIVED
STATE CORPORATION COMMISSION

07-16-81
JUL 16 1981

API Number 15-051-21 CONSERVATION DIVISION
WICHITA, KANSAS

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name HELSON CASING PULLING

Complete Address BOX 176 CHASE, MANA. 67524

Lease Name PAGET Well No. #1

Location SE-NW-SE Sec. 9 Twp. 13 Rge. 19 (East) (West)

County ELLIS Total Depth 3609 FT.

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor HELSON CASING PULLING

Address BOX 176 CHASE MANA. License No. _____

Operation Completed: Hour: 10:40 AM Day: 15th Month: JULY Year: 19 81

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows:

8 7/8" - 222 FT SB CUL. 1/4" 175ST CNT. → 4 1/2" SET @ 3607 FT. 1/4" 100ST CNT.
NO PLUG. RACH. → OPEN HOLE 2 FT
HELSON PUT SAND @ BOTTOM TO 3550 FT AND 1/4ST CNT. -
RECOVERED 800 FT PIPE - PIPE PULLED INTO.
ORDERED 140ST 50% POZ MIX. 4% GEL - 3% CA-CL. → 22ST GEL. → 4ST HULLS.
FIND 8 7/8" PLUG. → PUMPED CEMENT IN 8 7/8" WITH PUMP TRUCK.
PUT IN - 4ST HULLS. → 15ST GEL. → 80ST CNT. → 7ST GEL.
RELEASED PLUG. AND 60ST CNT. - MAX PRESSURE 200 LBS
CEMENTED BY ALLIED CNT.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: MARVIN SCHMIDT
Conservation Division Agent

DATE 8-25-81

INV. NO. 6256-W