

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

15-051-00587-00-00

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 42-31

LOCATION SW NW SW  
SEC. 29 TWP. 13 RGE. 19

Dry Hole  Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. A-1 Lease Bemis "A"

Operator Sterling Drg Co Address Box 127 Sterling, Kans

Field \_\_\_\_\_ County Ellis

Total Depth 3880 Feet.

Plugging Contractor R & D Casing Pulling

Plugging Contractor's License No. 236

Address \_\_\_\_\_

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 200' circulated with cement - 5 1/2" at 3601 with 75 sax  
cement behind - P.B. to 3564', perforated 3537'.

Filled with sand to 3520', set 4 sax cement with dump bailer,  
pulled 2930' 5 1/2" to 1100', circulated hole with heavy commercial  
mud at 1100', displaced 25 sax cement through 5 1/2" at 600', mud to  
185', displaced 20 sax cement through 5 1/2" at 185', heavy mud to  
35', set rock and 10 sax cement to bottom cellar.

Mudding and Cementing by Sun Cementing Co.

*Edward Petty*  
District Conservation Agent

Date 9-17-57

RECEIVED  
STATE CORPORATION COMMISSION

SEP 23 1957  
09-23-57  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC. 29 T. 13 R. 19  
BOOK PAGE 42 LINE 31