



15-051-20960-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 15 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Weiler of Shields Drlg. has this

date requested permission to plug the following described well:

Mr. Weiler guarantees payment of the plugging fee.

Operator's full Name: Shields Oil Producers

Complete Address: Shields Bldg., Russell, Kansas

Lease Name: Polifka Well No. 1

Location: SW NE SW Sec. 13 Twp. 13 Rge. (E)(W) 18

County: Ellis Total Depth 3445' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Weiler was instructed to plug the well as follows:

Gun pits, circulate heavy mud, displace 50 sk cmt at 500' thru drill
pipe. Heavy mud to 240' set cementing plug and displace 20 sk cmt thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk
cmt to base of cellar.

Very truly yours,

Leo F. Massey
Conservation Division Agent