

State of Kansas



FORM CP-2

15-051-22580-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Wilbur Cotton of Big Springs Drilling, Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Green Oil Operations

Complete Address: Box 503, Hays, Kansas 67601

Lease Name: Schenk Well No. #1

Location: SW/NW/NW Sec. 19 Twp. 13 Rge. 18 (E) (W)

County: Ellis Total Depth: 3705'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Wilbur Cotton was instructed to plug the well as follows:

8 5/8"-265' s.p. cuc. w/150 sacks common-2% Gel.-3% Cal. Cl.

Ordered 125 sacks 50/50 posmix-4% Gel-3% Cal. Cl. and 8 5/8" plug.

Spotted with drill stem with heavy mud between all plugs.

1st plug @ 780' w/70 sacks cement

2nd plug @ 240' w/40 Sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement

5 sacks of cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION

Very truly yours,

OCT 26 1981


Conservation Division Agent

CONSERVATION DIVISION
Wichita, Kansas