



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 6 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Wayne Hamilton of Clinton Oil Co has this

date requested permission to plug the following described well:

Mr. Clinton Oil guarantees payment of the plugging fee.

Operator's full Name: Clinton Oil Co

Complete Address: 6810 W Highway 54 Wichita, Kansas

Lease Name: Gross Well No. 4-D

Location: SE SE SE Sec. 25 Twp. 13 Rge. (E) (W) 18


County Ellis Total Depth 3650 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. was instructed to plug the well as follows:

Pull 5 1/2" to 600' circulate hole with heavy mud - pull 5 1/2" to 500', displace 20 sax cement through 5 1/2" - pull pipe to 200' displace 20 sax cement through 5 1/2" - pull pipe and set bridge at 35' and cement to 0'

Very truly yours,


Conservation Division Agent