

State of Kansas



FORM CP-2

15-051-23072-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Buster Weilert ~~of~~ Michael D. Weilert has this
Oil Company
date requested permission to plug the following described well:

Operator's Full Name: Michael D. Weilert Oil Company

Complete Address: Box 988, Hays, Kansas 67601

Lease Name: Jim Nease Well No. #1

Location: SW NE SW Sec. 26 Twp. 13 Rge. 18 (E) (W)

County: Ellis Total Depth: 3630'

Abandoned Oil Well ☐ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☒ X

Other well as hereafter indicated:

Mr. Weilert was instructed to plug the well as follows:

8 5/8"-201' s.p. cuc. w/125 sacks common-2% Gel.-3% Cal. Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal. and 8 5/8"-plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 720' w/70 sacks cement

2nd plug @ 230' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement

Circulated 10 sacks of cement in rat hole.

Very truly yours,

RECEIVED
STATE CORPORATION COMMISSION

JUN 14 1982

CONSERVATION DIVISION
Wichita, Kansas

[Signature]
Conservation Division Agent