

State of Kansas



15:05:2017:00:00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Lattimer of Raymond Oil Co. Inc. has this
date requested permission to plug the following described well:

Mr. Lattimer guarantees payment of the plugging fee.

Operator's full Name: Raymond Oil Co. Inc.,

Complete Address: 410 4th Nat'l Bk. Bldg. Wichita, Kansas

Lease Name: Weber Well No. 2

Location: NE SW NE Sec. 4 Twp. 13 Rge. 19 (E)(W) X

County Ellis Total Depth 3178 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Lattimer was instructed to plug the well as follows:

Gun pits. circulate heavy mud, set cementing plug at 720' and displace
100 sc cement thru drill pipe. Heavy mud to 240' set cementing plug and
displace 35 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole with
2 sc cement.

RECEIVED
STATE CORPORATION COMMISSION

Very truly yours,

SEP 11 1967
9-11-67
CONSERVATION DIVISION
Wichita, Kansas

Leo F. Nasvejo
Conservation Division Agent