

STATE OF KANSAS
STATE CORPORATION COMMISSION
Wichita State Office Building
130 South Market, Room 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-177

API NUMBER 15051-02830-0000
drilled 6/11/63

LEASE NAME Johnson

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

3300 Ft. from S Section Line

2640 Ft. from E Section Line

LEASE OPERATOR R.P. Nixon Operations, Inc.

SEC. 9 TWP. 13S RGE. 19W (E)or(W)

ADDRESS 207 West 12th Street Hays, KS 67601

COUNTY Ellis

PHONE #(913) 628-3834 OPERATORS LICENSE NO. 5252

Date Well Completed 6/20/63

Character of Well oil

Plugging Commenced 9/19/96

(Oil, Gas, D&A, SWD. Input, Water Supply Well)

-Plugging Completed 9/19/96

The plugging proposal was approved on 9/19/96 (date)

by Marion Schmidt (KCC District Agent's Name).

Is ACO-1 Filed? No - too old If not, is well log attached? yes

Producing Formation L/KC Depth to Top 3435' Bottom 3678' T.D. 3797'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 7/8"	157'	None
				5 1/2"	3796'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Ran tubing to 1244' and pumped 25 sx 60/40 Poz, 10% gel, w/200# hulls. Pulled tubing to 944' and pumped 70 sx of same cement w/300# hulls. Cement circulated. Pulled tubing out of hole and tied onto 5 1/2" casing. Pumped down casing w/25 sx same cement w/100# pressure. Tied onto 5 1/2" annulus and pumped 130 sx same cement w/50# pressure. Job complete @ 10:15 a.m.

(If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor Jay-Lan Corporation License No. 5128

Address 207 West 12th Street Hays, KS 67601-3898

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R.P. Nixon Operations, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Dan A. Nixon (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Jolene H. Klaus

(Address) 207 West 12th St. Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 27th day of September, 19 96

Jolene H. Klaus
Notary Public

My Commission Expires: 2-5-98

L. J. DREILING and SONS, Inc.
VICTORIA, KANSAS

15-051-02830-00-00

WELL LOG

Company Leo J. Dreiling Oil Company
Victoria, Kansas
Farm Johnson No. 1

Sec. 9 Twp. 13 Rng. 19W

Location C 8/2 N/2

Total Depth 3797'

County Ellis County, Kansas

Comm. 6-11-63 Comp. 6-20-63

Elevation: D. F. 2118'

Contractor L. J. Dreiling & Sons, Inc.
Victoria, Kansas

G. R. 2113'

Casing Record	Cement Record
157' - - - - - 8 5/8"	100 sacks cement
3796' - - - - - 5 1/2"	150 sacks cement

Production:
Arbuckle

Figures Indicate Bottom of Formations

0 - 20	Rock
20 - 100	Surface Clay & Rock
100 - 156	Shale
156 - 466	Shale
466 - 900	Shale & Shells
900 - 1130	Sand & Shale
1130 - 1170	Shale
1170 - 1442	Shale
1442 - 1486	Anhydrite
1486 - 1510	Shale
1510 - 2185	Shale & Lime
2185 - 2272	Shale
2272 - 2300	Shale
2300 - 2476	Shale & Lime
2476 - 2630	Shale & Lime
2630 - 2765	Lime & Shale
2765 - 3030	Shale & Lime
3030 - 3205	Shale & Lime
3205 - 3315	Shale & Lime
3315 - 3418	Lime
3418 - 3478	Lime
3478 - 3500	Lime
3500 - 3535	Lime
3535 - 3580	Lime
3580 - 3600	Lime
3600 - 3650	Lime
3650 - 3735	Lime
3735 - 3795	Lime
3795 - 3797	Lime
3797	TD

STATE OF KANSAS)
COUNTY OF ELLIS) ss.

RECEIVED
KANSAS CORP COMM
1966 SEP 30 A 12:05

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc.,
upon oath states that the above and foregoing is a true and correct
copy from the Daily Drilling Report from your Johnson No. 1.

Leo F. Dreiling
LEO F. DREILING

Subscribed and sworn to before me this 18th day of July, 1963.

Robert Zimmerman
NOTARY PUBLIC

My Commission Expires: August 14, 1965