

STATE OF KANSAS  
STATE CORPORATION COMMISSION


15-051-00394-00-00  
WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Ellis County, Sec. 29 Twp. 13S Rge. 19 (W)

Location as "NE/CNW/SW" or footage from lines NW NE NW  
Lease Owner Sterling Drilling Company, et al  
Lease Name Bemis Well No. 1  
Office Address Sterling, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed June 24 19 59  
Application for plugging filed June 24 19 59  
Application for plugging approved June 24 19 59  
Plugging commenced June 24 19 59  
Plugging completed June 24 19 59  
Reason for abandonment of well or producing formation \_\_\_\_\_

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3870 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	200'	8-5/8"	203'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud. Circulated. Bottom plug set at 600' with 20 sacks cement. Top plug set at 180' with 15 sacks cement.

**RECEIVED**  
STATE CORPORATION COMMISSION  
JUL 1 1959  
07-01-59  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Group Exploration Company  
Address Sterling, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.  
F. A. Wuellner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. A. Wuellner  
F. A. Wuellner Sterling, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 30th day of June, 19 59



My Commission Expires Jan. 22, 1962

Bernard Laudermilch  
Notary Public.

**PLUGGING**  
FILE SEC 22 T 13 R 19 W  
BOOK PAGE 48 LINE 23

GROUP EXPLORATION COMPANY  
Sterling, Kansas

WELL LOG - - - - - 15-051-00394-00-00 - - - - - BEMIS #1  
Located: NW NE NW, Section 29-13S-19W, Ellis County, Kansas

OWNER: Sterling Drilling Company, et al  
ROTARY DRILLING CONTRACTOR: Group Exploration Company

COMMENCED: 6-15-59  
COMPLETED: 6-24-59

TOTAL DEPTH: 3870'

LOG

0 - 80	Rock & Clay
80 - 200	Shale
200 - 675	Shale & Shells
675 - 910	Sand & Shale
910 - 1500	Red Bed & Shale
1500 - 1540	Anhydrite
1540 - 1550	Shale
1550 - 1860	Shale & Lime
1860 - 2220	Shale
2220 - 2400	Shale & Lime
2400 - 2955	Lime
2955 - 3255	Shale & Lime
3255 - 3870	Lime T.D.

CASING RECORD

Set 8-5/8" surface casing @ 200'  
with 165 sacks Pozmix, 2% c.c.

PRODUCTION RECORD

Plugged & Abandoned

**RECEIVED**  
STATE CORPORATION COMMISSION  
JUL 1 1959  
CONSERVATION DIVISION  
Wichita, Kansas

**PLUGGING**  
FILE SEC 29 T. 13 R. 19 W  
BOOK PAGE 48 LINE 23