


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-051-04772-00-00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ellis County. Sec. 33 Twp. 13 Rge. 19 (E) (W)
Location as "NE/CNW/SW" or footage from lines NW NW NW
Lease Owner Petro-Atlas, Inc.
Lease Name Bemis Well No. 1
Office Address 2000 Nat'l. Bank of Tulsa Bldg., Tulsa 3, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 12 19 59
Application for plugging filed September 12 19 59
Application for plugging approved September 12 19 59
Plugging commenced September 12 19 59
Plugging completed September 12 19 59
Reason for abandonment of well or producing formation Too low structually

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation Depth to top Bottom Total Depth of Well 3890' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	258.13'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 660'. Set plug. Put in 20 sacks cement. Filled to 180'. Set plug. Put in 1/2 sack hulls and 20 sacks cement. Filled with heavy mud up to 30'. Set plug. Filled to top with 1/2 sack hulls and 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP 25 1959

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor C-G Drilling Co.
Address 107 Rule Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
G. F. Galloway (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. F. Galloway
107 Rule Building
(Address)

SUBSCRIBED AND SWORN to before me this 16th day of September, 1959

My commission expires May 20, 1963

Vicky Jacobs
Vicky Jacobs Notary Public.

PLUGGING

File Sec. 33 T 13 R 19W

Book Page 4 Line 29

WELL LOG 15-051-04772-00-00

OPERATOR Petro-Atlas, Inc. SEC. 33-13-19W
 WELL NAME Bemis #1 LOC. NW NW NW
 TOTAL DEPTH 3890' COUNTY Ellis
 COMM. 9/1/59 COMP. 9/12/59 STATE Kansas
 RIG NO. 2 ELEVATION 2211' K.B.

CASING: Ran 258.13' (8 jts.) 8-5/8" OD Surface Casing. PRODUCTION: D & A

All measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	1065	Shale-Sand		
1065	1255	Sand-Shale		
1255	1536	Red Bed		
1536	1575	Anhydrite.		
1575	2150	Shale-Shell		
2150	2450	Lime-Shale	0° - 2500	
2450	2650	Shale-Lime	0° - 2750	
2650	3666	Lime-Shale	0° - 3000	
3666	3882	Lime	0° - 3250	
3882	3890	Arbuckle		

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 25 1959
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS }
 COUNTY OF SEDGWICK } SS.

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By G. F. Galloway
 G. F. Galloway

SUBSCRIBED AND SWORN TO, BEFORE ME, THIS 16th day of September, 1959.

My commission expires:
 May 20, 1963

Vicky Jacobs
 Vicky Jacobs - Notary public

PLUGGING

File Sec. 33 T B R 19W

Book Page 4 Line 29

