


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

15-051-30043-00-00  
**WELL PLUGGING RECORD**

NORTH



Locate well correctly on above  
Section Plat

Ellis County. Sec. 33 Twp. 13S Rge. 19W (E) (W)  
Location as "NE/CNW%SW%" or footage from lines NW NW SW  
Lease Owner Frontier Oil Company  
Lease Name Bemis Well No. 1  
Office Address 1720 Wichita Plaza, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed April 10, 19 65  
Application for plugging filed April 10, 19 65  
Application for plugging approved April 10, 19 65  
Plugging commenced April 10, 19 65  
Plugging completed April 10, 19 65  
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3906 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	216'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

20 sx cement @ 540' thru D.P.  
20 sx cement @ 210' thru D.P.  
Mud to 35'  
Plug, Hulls - cement to base  
of cellar, 2 sx in rathole.

**RECEIVED**  
STATE CORPORATION COMMISSION

APR 15 1965

0445-65

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling Company  
Address Box 173 -- Russell, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Maxine V. Head (employee of owner) ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Maxine V. Head

1720 Wichita Plaza, Wichita, Kansas  
(Address)

Subscribed and sworn to before me this 14th day of April, 19 65

Jean Hollan  
Notary Public.



RECEIVED  
STATE CORPORATION COMMISSION

APR 15 1965

15-051-30043-0000  
DRILLERS LOG

CONSERVATION DIVISION  
Wichita, Kansas

Bemis No. 1

CASING RECORD: 8 5/8" @ 216' w/135 sx cement

COMPANY: Frontier Oil Company

CONTRACTOR: Red Tiger Drilling Co.

COMMENCED: April 1, 1965

COMPLETED: April 9, 1965

DESCRIPTION: NW NW SW 33-13S-19W Ellis Co., Kansas

ELEVATION: 2246 GL 2251 RB

TOTAL DEPTH: 3906'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay Rock, Chalky Rock	0	.130	
Sandy Rock, Shale	130	217	
Shale	217	750	
Shale & Sand Streaks	750	888	
Hard Sandy Lime	888	890	
Shale & Shells	890	1547	
Anhydrite	1547	1590	
Shale & Shells	1590	2025	
Shale	2025	2175	
Lime & Shale	2175	2570	
Lime (Hard)	2570	2585	
Lime & Shale	2585	3000	
Shale & Lime Shells	3000	3080	
Lime	3080	3511	
Shale	3511	3514	
Lime	3514	3805	
Conglomerate	3805	3903	
Arbuckle	3903	3906	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

FRONTIER OIL COMPANY

Maxine V. Head  
Maxine V. Head

Subscribed and sworn to before me this 14th day of April, 1965.

Jeann Holman  
Notary Public

My Commission Expires: \_\_\_\_\_

5-22-66