


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15:051:00587:00:00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ellis County. Sec. 29 Twp. 13 Rge. (E) 19 (W)
Location as "NE/CNW/SW" or footage from lines SW - NW - SW
Lease Owner Sterling Drilling Company
Lease Name Bemis "A" Well No. 1
Office Address Sterling, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 8-8- 19 57
Application for plugging filed 9-5 19 57
Application for plugging approved 9-14 19 57
Plugging commenced 9-14 1957
Plugging completed 9-17- 1957
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	200	None
				5 1/2	3601	3074.22

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded hole to 3520' - dumped 4 sks cement - pulled casing to 1000' - circulated with mud - pulled to 600' - spotted 25 sks cement - pulled to 185' - spotted 20 sks cement - bailed off 35' of fluid - set rock bridge - dumped 10 sks cement.

RECEIVED
STATE CORPORATION COMMISSION
09-28-57
SEP 28 1957
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor R & D Casing Pulling Company License # 236
Address Box 569 Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.
F. A. Wuellner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) *F. A. Wuellner*
Sterling, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 27th day of September, 1957

My Commission Expires Jan. 22, 1958

My commission expires

Bernard Laudermilk
Notary Public.



PLUGGING
FILE SEC 29 T.13 R.19.W
BOOK PAGE 42 LINE 31

STERLING DRILLING COMPANY
Sterling, Kansas

WELL LOG ----- LS:051-00587-00-00 ----- BEMIS A-1
Located: SW NW 34, Section 29-13-19W, Ellis County, Kansas

OWNER: Sterling Drilling Company, et al
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company
CABLE TOOL CONTRACTOR: K. Smith Cable Tools

COMMENCED (r.d.): 7-15-57
(c.t.): 7-29-57

COMPLETED (r.d.): 7-27-57
(c.t.): 8-8-57

ROTARY TOTAL DEPTH: 3880'

LOG

0 - 200	Rock
200 - 590	Shale & Shells
590 - 675	Shale
675 - 1200	Sand
1200 - 1505	Shale & Shells
1505 - 1545	Anhydrite
1545 - 2365	Shale & Shells
2365 - 2495	Shale & Lime
2495 - 2585	Lime
2585 - 3185	Shale & Lime
3185 - 3280	Lime
3280 - 3365	Lime & Shale
3365 - 3460	Lime
3460 - 3515	Lime & Shale
3515 - 3555	Lime
3555 - 3600	Lime & Shale
3600 - 3675	Lime
3675 - 3700	Lime & Shale
3700 - 3725	Lime
3725 - 3840	Lime & Shale
3840 - 3863	Conglomerate
3863 - 3880	Arbuckle T. D.

CASING RECORD

Set 8-5/8" surface casing @ 200'
with 140 sacks cement, 200# c.c.

Set 5-1/2" casing @ 3601'
with 75 sacks cement.

CABLE TOOL INFORMATION M. I. O. T. Swabbed hole down. Drilling cement. Perforated from 3537' to 3542' with 20 jet shots. Acidized with 55 gal. 15% mud acid. Perforated from 3542' to 3548' with 24 jet shots. Swabbed hole down. Recovered 7.10 gal. fluid, 70% oil. Acidized with 2000 gal. acid. Swabbed hole down. Recovered 3.34 bbl. oil. P. O. P.

SEP 3 1957
DIVISION

PLUGGING	
FILE	SEC. 29 T. 13 R. 19W
BOOK	PAGE 42 LINE 31