


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

15.051.19333.00.00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ellis County. Sec. 27 Twp. 13 Rge. 19 (E) (W)
Location as "NE/CNW/SW" or footage from lines SW SW SW
Lease Owner Brunson Drilling Company, Inc.
Lease Name Bemis Well No. 1
Office Address 333 First Nat'l Bank Bldg, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 17 19 54
Application for plugging filed " " 19 "
Application for plugging approved " " 19 "
Plugging commenced " " 19 "
Plugging completed " " 19 "
Reason for abandonment of well or producing formation D&A

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3352 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 189' | none |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded hole to 184'. Set plug. Cemented with 15 sacks of cement and 1/2 sack of hulls. Set plug at 40'. Poured in 1/2 sack of hulls and 10 sacks cement. Filled plug to top. All plugs secured with 2 strands of .066 HOWCO steel line

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pam-Kar Drilling Company, Inc.
Address 333 First National Bank Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Ralph B. McLaughlin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ralph B. McLaughlin
333 First Nat'l Bank Bldg, Wichita, Ks. (Address)

SUBSCRIBED AND SWORN to before me this 23rd day of April, 19 54
My commission expires Sept. 4, 1957

Notary Public.

24-7366-S 3-53-20M

PLUGGING

FILE SEC 22 13 19
BOOK PAGE 29 LINE 6

BRUNSON DRILLING COMPANY
WICHITA
KANSAS

15051-19383-00 00

Well: Bemis # 1

Commenced Rd 4-6-54
Completed RD 4-13-54

Total Depth : 3352

D & A

Casing: 189' 8 5/8" OD 24 #

SW SW SW
Sec. 29-13-19
Ellis County

Elevation: 2172 DE

Contractor: Pam-Kar Drlg. Co.

| <u>STRATA</u> | <u>DEPTH</u> | <u>TOPS</u> |
|------------------------|--------------|-------------|
| Surface soil | 08 | |
| Rock & soil | 50 | |
| Shale | 75 | |
| Shale & shells | 200 | |
| Shale | 270 | |
| Shale & shells | 623 | |
| Sand & shale | 684 | |
| Shale & red bed | 726 | |
| Sand & shale | 1230 | |
| Pyrite shale | 1280 | |
| Pyrite, shale & shells | 1350 | |
| Shale & red bed | 1475 | |
| Anhydrite | 1495 | |
| Shale & shells | 1795 | |
| Salt & shale | 2010 | |
| Shale | 2070 | |
| Broken Lime | 2740 | |
| Shale & Lime | 2824 | |
| S hale & shells | 3195 | |
| Shale, sand, & Lime | 3305 | |
| Lime & shale | 3352 | |
| Total Depth | 3352 | |

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling reports.

BRUNSON DRILLING COMPANY, INC.
BY

Ralph B. McLaughlin
RALPH B. MCLAUGHLIN (Sec. Treas)

Signed and sworn to in my presence this 23rd day of April, 1954, by Ralph B. McLaughlin, Secretary-Treasurer of the Brunson Drilling Company, Inc., a corporation in the State of Kansas.

John T. Lee
NOTARY PUBLIC

My commission expires September 4, 1957.

