


15:05:30066:00:00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ellis County, Sec. 33 Twp. 13S Rge. 19W (E) (W)

Location as "NE/CNW/SW" or footage from lines SE SW SW
Lease Owner Frontier Oil Company
Lease Name Bemis Well No. 2
Office Address 1720. Wichita Plaza, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 4, 19 65
Application for plugging filed June 4, 19 65
Application for plugging approved June 4, 19 65
Plugging commenced June 4, 19 65
Plugging completed June 4, 19 65
Reason for abandonment of well or producing formation D & A



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3876 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	208'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged hole w/20 sx cement
thru D.P. @ 540', 20 sx cement
thru D.P. @ 200', mud to 35',
plug 1/2 sx hulls. Cement to
base of cellar. 2 sx cement
in rathole.

RECEIVED
STATE CORPORATION COMMISSION

JUN 9 1965

06-09-65
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling Company
Address Box 173 -- Russell, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Maxine V. Head (employee of owner) or ~~(owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Maxine V. Head
1720 Wichita Plaza, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 8th day of June, 19 65
Jean Hollan
Notary Public.



15-051-30066-00-00

DRILLERS LOG

Bemis No. 2

CASING RECORD: 8 5/8" @ 208' w/135 sx cement

COMPANY: Frontier Oil Company

CONTRACTOR: Red Tiger Drilling Company

COMMENCED: May 26, 1965

COMPLETED: June 4, 1965

DESCRIPTION: SE SW SW 33-13S-19W Ellis Co., Ks.

ELEVATION: 2233 DF 2236 RB

TOTAL DEPTH: 3876'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Rock, Sand & Clay	0	125	
Shale	125	209	
Shale, Shells & Bentonite	209	690	
Shale & Shells	690	995	
Dakota	995	1215	
Redbed & Shale	1215	1520	
Anhydrite	1520	1567	
Shale & Shells	1567	1760	
Shale	1760	2120	
Lime & Shale	2120	3225	
Lime	3225	3490	
Shale	3490	3494	
Lime	3494	3740	
Lime & Shale	3740	3852	
Cong. Chertz & Lime & Sandy Arbuckle	3852	3876	

RECEIVED
STATE CORPORATION COMMISSION
JUN 9 1965
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

FRONTIER OIL COMPANY


Maxine V. Head

Maxine V. Head

Subscribed and sworn to before me this 8th day of June, 1965.

Jean Stollar

Notary Public



My Commission Expires:

5-22-66