

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give all Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

Barber County, Sec 3 Twp. 35S Rge. (E) 10 (W)

Location as "NE/CNW&SW" or footage from lines 330' in SW Lines of SE/4

Lease Owner SINCLAIR OIL & GAS COMPANY (SW SW SE)

Lease Name L. T. Helmley Well No. 1

Office Address P. O. Box 521, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed March 3rd, 19 55

Application for plugging filed (Verbal) March 3rd, 19 55

Application for plugging approved Verbal March 3rd, 19 55

Plugging commenced March 3, 19 55

Plugging completed March 4, 19 55

Reason for abandonment of well or producing formation Dry in all Zones

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Pratt, Kansas

Producing formation Arbuckle Depth to top 5457 Bottom 5488 Total Depth of Well 5488 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Red Bed & Sand		0	180			
Shale		180	235'	10-3/4	231'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

From: 5488'	To: 5100'	60 Sacks Cement, thru Open End Drill Pipe
" 5100'	To: 210'	Rotary Mud, thru Open Drill Pipe
" 210'	To: 200'	Cement (10 Sacks)
" 200'	to 30'	Mud
" 30'	To 0	30 Sacks Cement TOTAL Cement 100 Sacks

RECORDED
STATE OF KANSAS
MARCH 30 1955
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Adkins Drilling Company, Inc.,
Address P. O. Box 724, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF Rice, ss.
I, W. B. Rhees (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. B. RHEES
Box 551, Chase, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 30th day of MARCH 19 55
My commission expires June 19 59



cc - M. A. Rives, State Plugging Supervisor
Sinclair Oil & Gas Company - Prod. Dept. - Tulsa (2)
Sinclair Oil & Gas Company - Geological Dept. Wichita
File

PLUGGING
FILE SEC 3 T 35 R 10 W
BOOK PAGE 102 LINE 9

DRILLERS LOG

Operator- SINCLAIR OIL & GAS CO.

Lease L. F. Helmley Lease C-25-55 Barber County, Kansas.

Contractor- Adkins Drilling Company, Inc. Great Bend, Kansas.

Formation	From	To	Formation	From	To
Red Bed & Sand	0	180	Lime & Chert	5195	5201
Shale	180	235	Lime & Shale	5201	5253
Set 231' of 10 3/4" Casing Cemented with 200 sacks common cement, 2% Strata Crete 2% Ca. Cl. cement circulated.			Lime & Sand	5253	5275
Plug and Cement	231-	235	Sand- Lime & shale	5275	5301
Red Bed and Shells	235	800	Lime & Sand	5301	5350
Shale & Shells	800	1050	Lime & Shale	5350	5391
Shale and Lime shells	1050	1510	Sand & Shale	5391	5431
Shale & Shells	1510	1600	Sand & Lime	5431	5479
Shale & Lime	1600	1915	Lime (Arbuckle)	5479	5488
Lime (F. Riley)	1915	2040	(Top of Arbuckle 5457')		
Shale & Lime	2040	2285	Total Depth	5488'	
Shale	2285	2371			
Lime & Shale	2371	2495	Hole Dry and Plugged.		
Shale & Shells	2495	2780			
Shale & Lime	2780	3168			
Lime & Shale	3168	3726			
Lime Shale	3726	3835			
Shale & Lime Streaks	3835	3920			
Sand & Sand	3920	4052			
Shale & Lime	4052	4272			
Lime & Chert	4272	4398			
Lime	4398	4715			
Cored 4715- 4767 Rec. 52ft. core					
Cored 4767 - 4806 Rec. 38' core					
Shale & Sand	4806	4849			
Cherty Lime	4849	4907			
Lime & Chert	4907	4932			
Lime	4932	4939			
Lime & Chert	4939	4948			
Lime & Shale	4948	5110			
Lime & Shale	5110	5132			
Shale & Lime	5132	5148			
Cored 5148 - 5172 Rec. 24 ft.					
Lime & Shale	5172	5185			
Lime	5185	5195			

RWD
03-30-55

State of Kansas.)
County of Barton) ss.

Jim Adkins, President of Adkins Drilling Company, Inc. deposes and says that the foregoing is a true and correct copy of the Drillers Log of Helmley No. 1, to the best of his knowledge and belief.

PLUGGING
FILE SEC 3 T. 35 R. 10W
BOOK PAGE 102 LINE 9

Subscribed and sworn to before me this 11th day of March 1955.

Jim Adkins

Pauline B. Adkins

Notary Public.