

STATE OF KANSAS  
NATURAL GAS CORPORATION COMMISSION  
100 S. Market, Room 2078  
Topeka, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-075-10056 20330  
LEASE NAME HCU

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1720-B

1320 Ft. from Section Line  
1320 Ft. from E. Section Line

LEASE OPERATOR Louis Dreyfus Natural Gas Corp.

SEC. 17 TWP. 22 RGE. 40W (E) or (W)

ADDRESS 1400 Quail Springs Pkwy., Suite 600 Okla. City, OK.

COUNTY Hamilton

PHONE# (405) 749-5287 OPERATORS LICENSE NO. 31321

Date Well Completed \_\_\_\_\_

Character of Well Oil

Plugging Commenced 10-15-98

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-19-98

The plugging proposal was approved on \_\_\_\_\_ (date)

by Kevin Strube (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 2800'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	222'	None
				4-1/2"	2800'	1 Jt.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each side. Plugged off bottom with sand to 2650' and 4 sacks cement. Ran 2" tubing to 1025', pumped 60 sks. cement, pulled tubing out, backed off 18' of 4-1/2" casing, ran 1 it. of tubing back in, pumped 15 sks. cement and circulated to surface. 60/40 pos. 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Louis Dreyfus Natural Gas Corp.

State of Kansas County of Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 3rd. day of November, 19 98

[Signature]  
Notary Public

My Commission Expires: \_\_\_\_\_

