

State of Kansas



FORM CP-2

15-051-23170-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

2007 Colorado Derby Building
WICHITA, KANSAS 67202

OCT 07 1982

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Pecilia Basgal of Drilling Res. Inc. has this

date requested permission to plug the following described well:

Operator's Full Name:

Drilling Resources Inc.

Complete Address:

RI Box 218 Victoria, Kans.

Lease Name:

Polifka

Well No.

#1

Location:

NE-NE-SE

Sec. 17

Twp. 13

Rge. 18

W (E) (W)

County:

Ellis

Total Depth:

3710 FT

Abandoned Oil Well

Gas Well

Input Well

SWD Well

D&A X

Other well as hereafter indicated:--

Mr. Basgal was instructed to plug the well as follows:

8 5/8" - 161 FT SP. Cnt. w/ 125 ST Quick Set. (By Sun Cnt.)
Order 150 ST 50/50 Pozmix 4% Gel - 3% Ca-Cl. End 8 5/8" Plug
spot with Drill Stem. With Heavy mud between all plugs.
1st Plug @ 420 FT w/ 80 ST Cnt.
2nd Plug @ 240 FT w/ 40 ST Cnt.
3rd Plug - Solid Bridge @ 40 FT w/ 10 ST Cnt.
10 ST In Rat Hole. (circulate)
10 ST In mouse hole. (circulate)

Marion J. Schmidt
Conservation Division Agent