

State of Kansas



FORM CP-2

15-051-22700-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Art Hunt of Kissinger Drilling Co. has this
date requested permission to plug the following described well:

Operator's Full Name: Petx Petroleum Corporation

Complete Address: 1700 Security Life Bldg., Denver, Colorado

Lease Name: Roth & Hassett Well No. #1

Location: 330' FSL 330' FWL Sec. 18 Twp. 13 Rge. 18 (E) (W)

County: Ellis Total Depth: 3776'

Abandoned Oil Well ☐ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☒

Other well as hereafter indicated:

Mr. Art Hunt was instructed to plug the well as follows:

8 5/8"-273' s.p. cuc. with 130 sacks common-2% Gel.-3% Cal. Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" ~~posmix~~ ^{RECEIVED}

Spot with drill stem with heavy mud between all plugs. STATE CORPORATION COMMISSION

1st plug @ 720' w/70 sacks cement

2nd plug @ 270' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement CONSERVATION DIVISION
Wichita, Kansas

Circualted 5 sacks ~~of~~ cement in rat hole and 5 sacks of cement in mouse hole.

Very truly yours,


Conservation Division Agent
Oral Orders given by Mr. Marian Schmidt

STATE OF KANSAS

15-051-22700-0000
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado, Derby Bldg.
Wichita, Kansas 67202-1286

INVOICE and WELL PLUGGING AUTHORITY

December 17, 1981

INVOICE NUMBER: 8762-W

TO: Petx Petroleum Corporation
1700 Security Life Bldg.
Denver, CO., 80202

PLUGGING ASSESSMENT AS FOLLOWS:

Roth & Hassett #1
SW SW SW, Sec. 18-13S-18W
Ellis
T.D. 3776'

PAYABLE UPON RECEIPT

\$122.72

NOTE: We also need the following before our file is completed:


☒ Well Plugging Record (CP-4)
☒ Well Log
☒ Well Plugging Application (CP-1)

WELL PLUGGING AUTHORITY

Gentlemen:

This is your authority to plug the above subject well in accordance with the rules and regulations of the state corporation commission.

This authority is void after ninety (90) days from the above date.


Administrator

Mr. Gilbert Scheck, 2202 Canterbury Rd., Hays, KS., 67601, (913) 628-2600

is hereby assigned to supervise the plugging of the above mentioned well.

RETURN PINK COPY WITH REMITTANCE