

State of Kansas



15-075-10014-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 24 1967
CONSERVATION DIVISION
Wichita, Kansas
02-24-67

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Valentine of Livingston Oil Co. has this

date requested permission to plug the following described well:

Mr. Valentine guarantees payment of the plugging fee.

Operator's full Name: Livingston Oil Company

Complete Address: Box 1797, Tulsa, Oklahoma

Lease Name: Unit 3021 Well No. 3021

Location: C NE /4 Sec. 30 Twp. 22 Rge. 41 (W)

County Hamilton Total Depth 2659' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Valentine was instructed to plug the well as follows:

8 5/8" to 107' circulated w/ cement. 4 1/2" to 2659' cemented.

Top perforations 2632' Plug bottom w/ 10 sacks cement

Top of cement 2480' Mud 2480' to 600'

Spotted 25 sacks cement 600' to 525' Mud 525' to 80'

Plug, Halls & 20 sacks Cement 80' to 0'.

Very truly yours,

Edward J. Eves
Conservation Division Agent