



JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JAN 24 1964

01-24-64  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Myers of Panhandle Development Co., Inc. has this date requested permission to plug the following described well:

Mr. Myers guarantees payment of the plugging fee.

Operator's full Name: Panhandle Development Co., Inc.

Complete Address: 801 Union Center. Wichita, Kansas

Lease Name: Jones Well No. 1-16

Location: C NE NE Sec. 16 Twp. 27 Rge. (E) (W) 34

County Haskell Total Depth 5151' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Myers was instructed to plug the well as follows:

8 5/8"-755' Circulated w/cement. 4 1/2"-5145' Cemented.

Plug back to 2890' w/iron plug, 1 sax.cement. Perforations-Top, 2814'

Plug bottom w/35 Sax.cement, stop cement at 1950' Mud 1950' to 648'

35 Sax.cement 648' to 548' Mud 548' to 45'

15 Sax.cement 45' to 0

Very truly yours,

*[Signature]*  
Conservation Division Agent