

State of Kansas



FORM CP-2

15-051-21631-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Steve Thomason of Ostrum Well Service Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Thomason Oil Co.

Complete Address: 27th. & Oak, Hays, Ks. 67601

Lease Name: Holt Well No. 1

Location: NE NE NE Sec. 16 13 Twp. 13 Rge. 19 (E) (W)

County: Ellis Total Depth: 3790'

Abandoned Oil Well XXX Gas Well Input Well SWD Well D&A

Other well as hereafter indicated:

Mr. Thomason was instructed to plug the well as follows:

8 5/8" 200' S.P. cnc w/ 200 sacks common. 4 1/2" casing set at 3790' with 200 sacks common. Plugged back to 3753'. Top perf. at 3136'. Set cast iron plug at 3100' with 1 sack cement on top. Shot pipe 2 times and recovered 2150'. Ordered 140 sacks 50/50 posmix 4% Gel., 3% Cal. Cl., 19 sacks Gel., 5 sacks of hulls and 8 5/8" plug. Pumped into 8 5/8" S.P. with pump truck 4 sacks hulls, 15 sacks Gel., 70 sacks cement, 4 sacks Gel., 1 sack hulls, released plug and followed with 70 sacks cement. Maximum Pressure 500 pounds

Very truly yours,

RECEIVED
STATE CORPORATION COMMISSION

[Signature]
Conservation Division Agent
Wichita Kansas
FEB - 9 1959