



15-051-22629-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Stan Lingreen of Revlin Drilling, Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Graham-Michaelis Corporation

Complete Address: Box 247, Wichita, Ks. 67201

Lease Name: Bemis Well No. #2-17

Location: Center of SW/SW/SW Sec. 17 Twp. 13 Rge. 19 (E) (W)

County: Ellis Total Depth: 3838'

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereafter indicated: _____

Mr. Stan Lingreen was instructed to plug the well as follows:

8 5/8"-339' sp. cuc. w/210 sacks common-2% Gel.-3% Cal. Cl.

Ordered 125 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spotted with drill stem with heavy mud between all plugs.

1st plug @ 720' w/70 sacks cement

2nd plug @ 330' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement

5 sacks of cement in rat hole.

Very truly yours,

Paul D. Schick
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION

OCT 19 1934

CONSERVATION DIVISION
Wichita, Kansas