


STATE OF KANSAS
STATE CORPORATION COMMISSION

15:05:21716:00:00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ellis County. Sec. 26 Twp. 13 Rge. 18WE/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines

C NE SW NE
Lease Owner Graham-Michaelis Corporation
Lease Name NUSS Well No. 1-26
Office Address P. O. Box 247, Wichita, Kansas 67201
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Locate well correctly on above
Section Plat

Date Well completed June 30 1979
Application for plugging filed (verbally) June 30 1979
Application for plugging approved (verbally) June 30 1979
Plugging commenced June 30 1979
Plugging completed June 30 1979

Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3650'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

T.D. 3650'
Set 1st plug at 550' with 70 sacks
2nd plug at 40' with 10 sacks
rathole with 5 sacks.
Cemented with 50/50 posmix, 6% gel.
Plug was down at 4:45 p.m., 6-30-79.

RECEIVED
STATE CORPORATION COMMISSION

JUL - 6 1979

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.
Jerry A. Langrehr, Executive Vice-President (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature)

801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of July, 1979,



Sherrie L. Brooks
Notary Public.

My commission expires 8-21-82

CONTRACTOR'S WELL LOG

15-051-21716-00-00

OPERATOR: Graham-Michaelis Corporation
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: Nuss #1-26
 LOCATION: C NE SW NE, Section 26-13-18W
 Ellis County, Kansas
 SPUD DATE: June 22, 1979
 COMPLETION DATE: June 30, 1979

0	570	Surface sand and shale
570	1328	Sand and shale
1328	1365	Anhydrite
1365	1900	Shale and red bed
1900	2233	Shale and shells
2233	2440	Shale
2440	3164	Shale and lime
3164	3310	Lime and shale
3310	3373	Shale and lime
3373	3510	Lime
3510	3535	Shale and lime
3535	3650	Lime
	3650	Rotary Total Depth

Spud hole at 5:30 p.m., June 22, 1979. Drilled 570' of 12 1/4" hole. Ran 16 joints of 8-5/8" new 24# casing. Set at 566.13' with 280 sacks of common cement, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 7:00 a.m., June 23, 1979.

T.D. 3650'. Set first plug at 550' with 70 sacks, second plug at 40' with 10 sacks, rathole with 5 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 4:45 p.m., June 30, 1979.

SAMPLE TOPS:

Anhydrite 1328'
 B/Anhydrite 1365'

RECEIVED
 STATE CORPORATION COMMISSION

JUL - 6 1979

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

CONSERVATION DIVISION
 Wichita, Kansas

Jerry A. Langrehr, Executive Vice-President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Nuss #1-26, C NE SW NE, Section 26-13-18W, Ellis County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jerry A. Langrehr
 Jerry A. Langrehr
 Executive Vice-President

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 3rd day of July, 1979.



Sherrie L. Brooks
 Sherrie Brooks, Notary Public

My commission expires 8-21-82.